

Change Order No. 07

| Project Name: Bunton Creek Road | Owner's Project No.: PO 0000002293(Lehman approach) |
|---|---|
| Project Owner and Address: City of Kyle 100 W. Center Street Kyle, Texas 78640 | Change Order Date of Issuance: June , 2017 |
| Project Contractor and Address: Aaron Concrete Construction, LP 4108 Nixon Lane Austin, Texas 78725 | Date of Contract: 8/17/16 Contract Period: 400 Days - 11/28/2016 to 1/2/2018 |

It is agreed to modify the Contract referred to above as follows:

| Item # | Description Of Changes – on Lehman Road | Deduct from Contract | Change in Contract Price | Change in Contract Time |
|--------|--|-------------------------|-----------------------------|----------------------------|
| 1 | Increase Excavation for Lehman work from Sta. 184+75 to 186+22.93 for placement of 8" HMA + 6" Flex Base & 2" Surf Mat to be placed under separate contract. Excavation from earthwork summary plan sheet 307 cy + Road Excavation (23 ft x 148 ft x 16" depth) 168 cy = 475 x \$12/cy = \$5,448.00. | | \$5,700.00 | |
| 2 | Increase Embankment for Lehman work from Sta. 184+75 to 186+22.93 from earthwork plan sheet 420 cy x \$12/cy = \$5,040.00. | | \$5,040.00 | |
| 3 | Addition of Geogrid Base Reinforcement (TY 2) Lehman Stations 184+75 to 186+22.93, 148 ft x 46 ft = 751 sy @ \$2.00/sy = \$1,502.00 | | \$1,502.00 | |
| 4 | Addition of 6"Flex Base Lehman Stations 184+75 to 186+22.93, 148 ft x 46 ft x 6" = 126 cy @ $$47.00/sy = $5,922.00$ | | \$5,922.00 | |
| 5 | Addition of Prime on Lehman Sta. 184+75 to 186+22.93, 148 ft x 46 ft = 151 gal.@ \$4.50/sy = \$679.50 | ч | \$679.50 | |
| 6 | Addition of TY B HMA for Lehman Sta. $184+75$ to $186+22.93 = 1$ st Lift (148 ft x 46 ft x 110 #/sy/in depth x 3" depth / 2000 #/ton) 125 tons + 2 ^{nd lift} (148 x 40 ft x 110#/sy/in depth x 3"/2000)109tons = 234 tons@\$90.00/ton = \$21,060.00 | - | \$21,060.00 | |
| 7 | Addition of TY D HMA for Lehman Sta. 184+75 to 186+22.93 = 148 ft x 40 ft x 110 #/sy/in depth x 2" depth / 2000 #/ton = 73 tons @\$89.00/ton = \$7,387.00 | 1 | \$6,452.50 | |
| 8 | Increase Excavation on Bunton through Lehman intersection from sta. 66+49 – 67+60 = 111 ft x 16" depth X 26 ft = 142.52 x \$12.00/cy = \$1,710.22 | | \$1,710.22 | |
| 9 | Addition of Geogrid Base Reinforcement (TY 2) through Bunton/Lehman intersection Stations 66+49 to 67+60, 111 ft x 26 ft = 320.67 sy @ \$2.00/sy = \$641.34 | - | \$641.34 | |
| 10 | Addition of 6"Flex Base on Bunton at Lehman intersection Stations 66+49 to 67+60.00, 111 ft x26 ft x 6" = 142.52 cy @ \$47.00/sy = \$6,698.37 | | \$6,698.37 | |
| 11 | Addition of Prime on Bunton at Lehman intersection Stations 66+49 to 67+60.00, 111 ft x26 ft = 320.67 sy x 0.20 gal/sy= 64 gal x \$4.50 = \$288.00 | | \$288.00 | |
| 12 | Addition of TY B HMA on Bunton from sta. 66+49 to sta. 67+60 = 111 ft = 1st Lift (111 ft x 24 ft x 110 #/sy/in depth x 3" depth / 2000 #/ton) 49 tons + 2nd lift (111 x 24 ft x 110#/sy/in depth x 3"/2000) 49tons = 98 tons@\$90.00/ton = \$8,820.00 | | \$8,820.00 | |
| 13 | Addition of TY D HMA on Bunton Sta. 66+49 to 67+60.00 = 111 ft x 24 ft x 110 #/sy/in depth x 4" depth / 2000 #/ton = 65 tons @\$89.00/ton = \$5,785.00 | 4 | \$5,785.00 | |
| 14 | Addition of curb and gutter from Lehman Sta. 184+75 to 186+22.93 = 148 ft x 2 sides = 296 ft @ \$13.00/ft = \$3,848.00 | (4) | \$3,848.00 | |
| 15 | Addition of retaining wall (concrete block) on west side of Lehman to be field measured for final payout estimated at 5.25' x 148 ft = 777 sq. ft x \$50.00/sq. ft = \$38,850 (per plans total 822.00 sq. ft to sta. 183+54) | , | \$38,850.00 | |
| 16 | Addition of Temp Sediment Control Fence (Install) Sta. 184+75 to 186+22.93 = 148 ft x 2 sides = 296 ft @ \$2.00 = \$592.00 | | \$592.00 | |
| 17 | Removal of Temp Sediment Control Fence Sta. 184+75 to 186+22.93 = 148 ft x 2 sides = 296 ft @ \$0.60 = \$177.60 | | \$177.60 | |
| 18 | Addition Broadcast Seeding 148 ft x 30 ft = 493 sy @ \$0.70 = \$345.10 | | \$345.10 | |
| 19 | Addition of Condt (PVC) Schd 40 (3") runs 7-4 65 ft, 7-6 70 ft, 7-8 75 ft, 7-5 50 ft, 7-12 70 ft = 330 ft @ \$12.00/ft = \$3,960.00 | | \$3,960.00 | |
| 20 | Addition of 4 Ground Boxes TY A w/ apron @ \$1000.00/ft = \$4,000.00 | | \$4,000.00 | |



| 21 | Addition of temp no passing center line striping reflective pavement marking TY I 4" Y solid 90 ml from Sta. 184+75 to 186+22.93 = 148 ft x 2 = 296 ft @ \$0.50 = \$148.00 | | \$148.00 | |
|----|--|----|--------------|------|
| 22 | Addition of temp turn lane striping reflective pavement marking TY I 8" W solid 90 ml from Sta. 184+75 to 186+22.93 = 148 ft @ \$1.30 = \$192.40 | * | \$192.40 | |
| 23 | Addition of stop bar at Lehman reflective 24" pavement marking TY I 24" W solid 90 ml 23 ft @ \$6.00 = \$138.00 | | \$138.00 | |
| 24 | Install small road signs and support (Stop & Turn lane designation at Lehman) 2 ea @ \$400.00 | | \$800.00 | |
| 25 | Addition of 3 - 18" RCP Pipe 40 ft length each for driveways at approximate stations 62+50, 65+90, & 66+50 = 120 ft x \$41.00/ft = \$4,920.00 | | \$4,920.00 | |
| 26 | Addition of 3 asphalt driveways at approximately 52 sy = 156 sy x \$51/sy = \$7,956.00 | | \$7,956.00 | |
| 27 | Increase of SETs 18" (4:1) for 3 asphalt driveways added = 6 ea x \$1,400/ea = \$5,600.00 | | \$5,600.00 | |
| | Sub-Totals = | \$ | \$141,826.03 | 0.00 |
| | Difference Net = | \$ | \$141,826.03 | 0.00 |

| | Contract Time prior to this Change Order | | | | | | |
|---|--|--|--|--|--|--|--|
| Summary: It is agreed to modify the Contract referred to above as follows: | Substantial (days and date): _350 days - 11-13-17 | | | | | | |
| Contract Price prior to this Change Order: \$\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\ | Final (days and date): _400 days - 1/2/18 | | | | | | |
| | | | | | | | |
| | Net Increase (decrease) of this Change Order | | | | | | |
| Net Increase (decrease) of this Change Order: \$\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\ | days | | | | | | |
| | | | | | | | |
| | Revised Contract Time with all approved Change Orders | | | | | | |
| Revised Contract Price with all approved Change Orders: \$4,646,302.60 | Substantial (days and date): _350 days - 11/13/17 | | | | | | |
| Revised Contract Free With an approved Change Creates C | Final (days and date): 400 days - 1/2/18 | | | | | | |
| | | | | | | | |
| The changes included in this Change Order are to be accomplished in accordance with the | e terms, stipulations and conditions of the original Contract as | | | | | | |
| though included therein. | | | | | | | |
| · | | | | | | | |
| | Data | | | | | | |
| Accepted for Contractor by: [Aaron Concrete Construction, LP] | Date: | | | | | | |
| | | | | | | | |
| Recommended for Approval by: Brian Young, P.E., Engineer of Record | Date: | | | | | | |
| | | | | | | | |
| | | | | | | | |
| Approved for Owner by: City Engineer | Date: | | | | | | |
| | | | | | | | |
| Attest for Owner by: (City Secretary) | Date: | | | | | | |
| | | | | | | | |
| Distribution: Contractor File Field | Owner Other | | | | | | |