

Park at Plum  
Creek

Kyle, Texas

ConstructionSet

NOTES

- ALL PLANT MATERIAL LOCATIONS SHALL BE STAKED IN FIELD BY CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER PRIOR TO INSTALLATION.
- THE CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM ALL SITE FEATURES.
- ALL DISTURBED AREAS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE HYDROMULCHED WITH A NATIVE SEED MIX USING HYDRAULICALLY-APPLIED HIGH PERFORMANCE FLEXIBLE GROWTH MEDIUM, AS DESCRIBED IN THE SPECIFICATIONS.
- SEE SPECIFICATIONS FOR SEED MIX PLANTING DATES. THESE DATES CANNOT CHANGE.
- GRASSING QUANTITIES ARE APPROXIMATE AND CONTRACTOR IS RESPONSIBLE FOR ALL AREAS DESIGNATED ON PLANS.
- FINE GRADING SHALL BE PERFORMED IN ALL AREAS TO BE SEEDED. FINE GRADING SHALL INCLUDE THE REMOVAL OF DEBRIS, ROCKS, ETC. FROM THE SITE.
- THE CONTRACTOR SHALL VERIFY LOCATIONS OF AND PROTECT ALL UTILITIES IN THE FIELD PRIOR TO COMMENCEMENT OF WORK.
- SEE SHEET LX.XX FOR PLANTING DETAILS AND PLANT SCHEDULE.
- ALL CONTAINER GROWN NURSERY STOCK SHALL BE HEALTHY, VIGOROUS, WELL ROOTED, AND ESTABLISHED IN THE CONTAINER IN WHICH IT IS GROWING. CONTAINER GROWN NURSERY STOCK SHALL HAVE A WELL-ESTABLISHED ROOT SYSTEM REACHING THE SIDES OF THE CONTAINER TO MAINTAIN A FIRM BALL WHEN THE CONTAINER IS REMOVED, BUT SHALL NOT HAVE EXCESSIVE ROOT GROWTH ENCIRCLING THE INSIDE OF THE CONTAINER.

Mark	Date	Description
△		

NLAI Job #: 17019  
Drawn by: MAP  
Checked by: JT  
Date of Issue: 01.08.18

Sheet Title:

Planting  
Plan

Sheet No.:

L3.00

